



PLAN - INTERMEDIATE BENT

SCALE 3/8" = 1'-0"



PLAN - END BENT

SCALE 3/8" = 1'-0"



HALF ELEVATION - INTERMEDIATE BENT

SCALE 3/8" = 1'-0"

HALF ELEVATION - END BENT

SCALE 3/8" = 1'-0"

ESTIMATED QUANTITIES (ONE INTER. BENT)


BAR NO.	UNIT LENGTH	TOTAL LENGTH	LOCATION
801	6	30'-2"	LONGIT. IN CAP
802	6	8'-8"	LONGIT. IN CAP BTW. PILES
TOTAL NO. 8 BARS = 233'-0" = 622 LBS.			
601	19	2'-0"	DOWELS
TOTAL NO. 6 BARS = 38'-0" = 57 LBS.			
501	2	30'-2"	LONGIT. IN CAP
TOTAL NO. 5 BARS = 60'-4" = 63 LBS.			
401	37	8'-2"	STIRRUPS IN CAP
402	4	3'-4"	STIRRUPS IN RISER
403	2	2'-0"	LONGIT. IN RISER
TOTAL NO. 4 BARS = 319'-6" = 213 LBS.			
DEFORMED REINFORCING STEEL = 955 LBS.			
* CLASS A1 CONCRETE = 5.10 CU. YDS.			
MAX. PILE LOAD: SERVICE DEAD LOAD = 23 TONS			
SERVICE LIVE LOAD = 36 TONS			
FACTORED TOTAL LOAD = 81 TONS			

* ADD 57 LBS. OF REINFORCING STEEL (19-601 DOWELS) WHEN TWO FIXED ENDS OCCUR ON THE SAME BENT.

ESTIMATED QUANTITIES (ONE END BENT)


BAR NO.	UNIT LENGTH	TOTAL LENGTH	LOCATION
801	6	30'-2"	LONGIT. IN CAP
802	6	8'-8"	LONGIT. IN CAP BTW. PILES
TOTAL NO. 8 BARS = 233'-0" = 622 LBS.			
601	19	2'-0"	DOWELS
TOTAL NO. 6 BARS = 38'-0" = 57 LBS.			
501	2	30'-2"	LONGIT. IN CAP
TOTAL NO. 5 BARS = 60'-4" = 64 LBS.			
401	37	8'-2"	STIRRUPS IN CAP
402	4	3'-4"	STIRRUPS IN RISER
403	2	2'-0"	LONGIT. IN RISER
404	8	8'-9"	STIRRUPS IN WINGWALL
405	8	2'-10"	LONGIT. IN WINGWALL
406	12	4'-0"	LONGIT. IN WINGWALL
TOTAL NO. 4 BARS = 460'-2" = 307 LBS.			
DEFORMED REINFORCING STEEL = 1050 LBS.			
CLASS A1 CONCRETE = 5.92 CU. YDS.			
MAX. PILE LOAD: SERVICE DEAD LOAD = 23 TONS			
SERVICE LIVE LOAD = 36 TONS			
FACTORED TOTAL LOAD = 81 TONS			

Ø 16" # PPC PILES USED FOR ESTIMATING PURPOSES ONLY. (ADD 0.04 CU. YDS. OF CLASS A1 CONCRETE PER BENT WHEN 14" # PPC PILES ARE USED.)




SECTION A-A

SCALE: 3/4" = 1'-0"



SECTION B-B

SCALE: 3/4" = 1'-0"






END ELEVATION

SCALE 3/4" = 1'-0"

NOTES:
 DESIGN SPECIFICATIONS: AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, 4th EDITION, WITH 2008 & 2009 INTERIMS.
 DESIGN LOAD: LIVE LOAD IS HL-93, AND LADV-11 (LOUISIANA DESIGN VEHICLE LIVE LOAD 2011).
 STRUCTURAL CONCRETE: ALL CONCRETE SHALL BE CLASS A1. EXPOSED EDGES SHALL HAVE A 3/4" CHAMFER UNLESS SPECIFIED OTHERWISE. ALL EXPOSED FACES OF WINGWALLS AND ENDS OF CAPS SHALL RECEIVE A SURFACE FINISH AS PER THE SPECIFICATIONS UNLESS SPECIFIED OTHERWISE.
 REINFORCING STEEL: ALL REINFORCING SHALL BE GRADE 60. DIMENSIONS RELATING TO FABRICATION ARE OUT TO OUT OF BARS, UNLESS SPECIFIED OTHERWISE. DIMENSIONS RELATING TO SPACING ARE TO BAR CENTERS, UNLESS SPECIFIED OTHERWISE. DOWELS (601 BARS) SHALL BE PROVIDED AT ALL FIXED BEARINGS AND APPROACH SLAB BEARINGS. ALL EXPOSED ENDS OF DOWELS SHALL BE WRAPPED WITH TWO LAYERS OF 15 LB. ASPHALT SATURATED FELT. CLOSE FITTING TUBES OF COMPRESSIBLE MATERIAL NOT LESS THAN 3/16" THICK MAY BE SUBSTITUTED.
 PRECAST CONCRETE PILES: CONFORM TO PILE STANDARD PLAN AND PROJECT PLANS FOR FABRICATION AND INSTALLATION. PILES WILL BE PAID FOR UNDER THE DESIGNATED PILE PAY ITEMS.
 PREFORMED JOINT MATERIAL: PREFORMED JOINT MATERIAL SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS.
 PAYMENT: ALL OTHER WORK WILL BE PAID FOR UNDER THE DESIGNATED BRIDGE SUPERSTRUCTURE AND SUBSTRUCTURE PAY ITEM AND IN ACCORDANCE WITH THE SPECIFICATIONS.

AS-DESIGNED RATING		
VEHICLE	RATING FACTOR	NOTES
HL-93 (INV)	1.417	---
HL-93 (OPR)	1.836	---
LADV-11 (INV)	1.090	MAGNIFICATION FACTOR = 1.3



SHEET NUMBER: []

DESIGN: B. DELATTE

CHECK: J. NAKHLEH

DETAIL: D. HYMEL

CHECK: J. NAKHLEH

REVIEW: []

SERIES: 1 OF 11

APPROVED BY CHIEF ENGINEER: [Signature]

DATE: 12/10/2025

REVISION OR CHANGE ORDER DESCRIPTION: []

NO. []

DATE []

STATE PROJECT: []

REINFORCED CONCRETE PILE BENT

28'-0" CLEAR ROADWAY


90° CROSSING TWO WAY TANGENT

PSS-90-28-20SL


DOT

LOUISIANA DEPARTMENT OF TRANSPORTATION & DEVELOPMENT

STANDARD PLAN




SECTION A-A
SCALE 3/8" = 1'-0"




HALF SECTION
SHOWING SPACING OF
TOP TRANS. REINF. STEEL
SCALE 3/8" = 1'-0"


HALF SECTION
SHOWING SPACING OF
BOTTOM TRANS. REINF. STEEL
SCALE 3/8" = 1'-0"




DETAIL B
SCALE 1/2" = 1'-0"



DETAIL SHOWING TYPICAL JOINT & HAUNCH
SCALE 1/2" = 1'-0"



DETAIL "A"
N.T.S.



SECTION B-B
SCALE 3/8" = 1'-0"


ESTIMATED QUANTITIES (ONE SPAN)				
BAR NO.	UNIT LENGTH	TOTAL LENGTH	LOCATION	
801	73	19'-7"	1429'-7"	LONGIT. BOT. OF SLAB
TOTAL NO. 8 BARS = 1429'-7" = 3817 LBS.				
501	56	5'-0"	280'-0"	TRANS. TOP OF SLAB
TOTAL NO. 5 BARS = 280'-0" = 292 LBS.				
401	25	19'-7"	489'-7"	LONGIT. TOP OF SLAB
402	56	30'-2"	1689'-4"	TRANS. TOP & BOT. OF SLAB
TOTAL NO. 4 BARS = 2178'-11" = 1456 LBS.				
TOTAL DEFORMED REINFORCING STEEL = 5565 LBS.				
CLASS A1 CONCRETE = 25.48 CU. YDS.				
CONCRETE RAILING (BARRIER TYPE) = 40.00 LIN. FT.				

AS-DESIGNED RATING		
VEHICLE	RATING FACTOR	NOTES
HL-93 (INV)	1.361	---
HL-93 (OPR)	1.764	---
LADV-11 (INV)	1.047	MAGNIFICATION FACTOR = 1.3

SPAN NOTES:
DESIGN SPECIFICATIONS:
 AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, 4th EDITION, WITH 2008 & 2009 INTERIMS.
DESIGN LOADS:
 THE BRIDGE DECK IS DESIGNED FOR A FUTURE WEARING COURSE OF 19 PSF. THE LIVE LOAD IS HL-93, AND LADV-11 (LOUISIANA DESIGN VEHICLE LIVE LOAD 2011).
STRUCTURAL CONCRETE:
 ALL CONCRETE SHALL BE CLASS A1. EXPOSED EDGES SHALL HAVE A 3/4" CHAMFER UNLESS SPECIFIED OTHERWISE. ALL BARRIER RAIL SURFACES ARE TO RECEIVE A CLASS 3 SPECIAL FINISH.
REINFORCING STEEL:
 ALL REINFORCING SHALL BE GRADE 60; DIMENSIONS RELATING TO SPACING ARE TO BAR CENTERS, DIMENSIONS RELATING TO FABRICATION ARE OUT TO OUT OF BARS, UNLESS SPECIFIED OTHERWISE. ALL REINFORCING BARS SHALL BE PLACED TO PROVIDE A MINIMUM COVER OF ONE INCH FROM THE SURFACE OF THE DRAIN HOLES TO THE FACE OF THE BARS.
GUARD RAIL:
 CONFORM TO PROJECT PLANS AND GUARD RAIL STANDARD PLANS.
PAYMENT:
 ALL WORK WILL BE PAID FOR UNDER THE DESIGNATED BRIDGE SUPERSTRUCTURE AND SUBSTRUCTURE PAY ITEM AND IN ACCORDANCE WITH THE SPECIFICATIONS.

FOR BRIDGES IN DISTRICT 04 & 05, MINIMUM CONCRETE COVER IN TOP OF SLAB SHALL BE 2 1/2".













SHEET NUMBER	PARISH	CONTROL SECTION	STATE PROJECT
DESIGN CHECK	J. NAKHLEH	DETAIL CHECK	D. HYMEL
APPROVED BY CHIEF ENGINEER:	REVISION OR CHANGE ORDER DESCRIPTION		DATE
SPAN (1 OF 2)		20'-0" CONCRETE SLAB SPAN	PSS-90-28-20SL
28'-0" CLEAR ROADWAY		90° CROSSING TWO WAY TANGENT	
STANDARD PLAN			



* 1'-0" (MIN.) SPLICE



BARRIER RAILING TRANSITION ELEVATION

(SHOWING BARRIER RAILING AT END OF BRIDGE)
SCALE: 1/2" = 1'-0"




BARRIER RAILING TRANSITION SECTIONS


SCALE: 3/4" = 1'-0"






SHEET NUMBER		PARISH		STATE PROJECT	
DESIGN	B. DELATTE	CONTROL SECTION			
CHECK	J. NAKHLEH	REVIEW	J. NAKHLEH		
DETAIL	D. HYMEL	DATE	12/10/2025		
REVISION		SERIES	3 OF 11		
APPROVED BY CHIEF ENGINEER:					
REVISION OR CHANGE ORDER DESCRIPTION					
NO. DATE					
SPAN (2 OF 2) 20'-0" CONCRETE BARRIER 28'-0" CLEAR ROADWAY 90° CROSSING TWO WAY TANGENT					
LOUISIANA DEPARTMENT OF TRANSPORTATION & DEVELOPMENT STANDARD PLAN					




SECTION A-A
SCALE 3/8" = 1'-0"




PLAN
SCALE 3/8" = 1'-0"




SECTION ALONG CL ROADWAY
SCALE: 3/8" = 1'-0"



DETAIL A
SCALE: 1/2" = 1'-0"



SAWING & SEALING JOINT DETAIL
N.T.S.



JOINT DETAIL
N.T.S.









ESTIMATED QUANTITIES (ONE SLAB)				
BAR NO.	NO.	UNIT LENGTH	TOTAL LENGTH	LOCATION
601	58	9'-7"	555'-10"	LONGIT. BOT. OF SLAB
602	20	28'-8"	573'-4"	TRANSV. BOT. OF SLAB
TOTAL NO. 6 BARS = 1,129'-2" = 1,696 LBS.				
401	32	9'-7"	306'-8"	LONGIT. TOP OF SLAB & CURB
402	11	28'-8"	315'-4"	TRANSV. TOP OF SLAB
403	14	2'-0"	28'-0"	DOWELS IN CURB
TOTAL NO. 4 BARS = 650'-0" = 434 LBS.				
TOTAL DEFORMED REINFORCING STEEL = 2,130 LBS.				
CONCRETE APPROACH SLAB = 32.22 SQ. YDS.				
ASPHALT CONCRETE = 3.0 TONS				
SAW CUT & SEAL = 27 LIN. FT.				

- TO BE PAID FOR UNDER ITEM CONCRETE APPROACH SLABS.
- REQUIRED WHEN APPROACH SLAB IS ADJACENT TO ASPHALT CONCRETE PAVEMENT.

APPROACH SLAB NOTES:

DESIGN SPECIFICATIONS: AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS 4th EDITION, WITH 2008 & 2009 INTERIMS.
 STRUCTURAL CONCRETE: ALL CONCRETE SHALL BE CLASS A1. EXPOSED EDGES SHALL HAVE A 3/4" CHAMFER, UNLESS SPECIFIED OTHERWISE.
 ASPHALT CONCRETE: TO BE THE SAME TYPE AS THE ASPHALT CONCRETE USED FOR THE APPROACH ROADWAY PAVEMENT OR OVERLAY.
 REINFORCING STEEL: ALL REINFORCING STEEL SHALL BE GRADE 60. DIMENSIONS RELATING TO THE FABRICATION ARE OUT-TO-OUT OF BARS, UNLESS SPECIFIED OTHERWISE. DIMENSIONS RELATING TO SPACING ARE TO BAR CENTERS.
 BEDDING MATERIAL: FOR DETAILS OF BEDDING MATERIAL AND UNDERDRAINS SEE APPROACH SLAB STANDARD DETAILS.
 SAWING & SEALING: THE ASPHALT CONCRETE SHALL BE SAW CUT AT THE END OF THE CONCRETE APPROACH SLAB THE ENTIRE ROADWAY WIDTH AND SEALED WHICH WILL BE PAID FOR UNDER THE DESIGNATED ROADWAY PAY ITEM.
 PAYMENT: ALL OTHER WORK WILL BE PAID FOR UNDER THE DESIGNATED BRIDGE CONCRETE APPROACH SLAB PAY ITEM AND IN ACCORDANCE WITH THE SPECIFICATIONS.

SHEET NUMBER		PARISH		CONTROL SECTION		STATE PROJECT	
DESIGN CHECK		REVIEW		DATE		SERIES	
B. DELATTE		J. NAKHLEH		12/10/2025		4 OF 11	
D. HYMEL		J. NAKHLEH					
APPROVED BY CHIEF ENGINEER:		REVISION OR CHANGE ORDER DESCRIPTION		NO.		DATE	
APPROACH SLAB		CONCRETE APPROACH SLAB		28'-0" CLEAR ROADWAY		90° CROSSING TWO WAY TANGENT	
10'-0" CONCRETE APPROACH SLAB						PSS-90-28-20SL	
DOTD		LOUISIANA DEPARTMENT OF TRANSPORTATION & DEVELOPMENT		STANDARD PLAN			



ESTIMATED QUANTITIES (ONE INTER. BENT)				
BAR NO.	UNIT LENGTH	TOTAL LENGTH	LOCATION	
801	6	30'-10"	185'-0"	LONGIT. IN CAP
802	6	8'-6"	51'-0"	LONGIT. IN CAP BTW. PILES
TOTAL NO. 8 BARS = 236'-0" = 630 LBS.				
501	2	30'-10"	61'-8"	LONGIT. IN CAP
TOTAL NO. 5 BARS = 61'-8" = 64 LBS.				
401	31	8'-2"	253'-2"	STIRRUPS IN CAP
403	6	6'-6"	39'-0"	STIRRUPS IN CAP
TOTAL NO. 4 BARS = 292'-2" = 195 LBS.				
TOTAL DEFORMED REINFORCING STEEL = 889 LBS.				
TOTAL CLASS A1 CONCRETE = 5.19 CU. YDS.				
MAX. PILE LOAD: SERVICE DEAD LOAD = 19 TONS				
SERVICE LIVE LOAD = 36 TONS				
FACTORED TOTAL LOAD = 75 TONS				

16" ϕ PPC PILES USED FOR ESTIMATING PURPOSES ONLY. (ADD 0.04 CU. YDS. OF CLASS A1 CONCRETE PER BENT WHEN 14" ϕ PPC PILES ARE USED.)




ESTIMATED QUANTITIES (ONE END BENT)				
BAR NO.	UNIT LENGTH	TOTAL LENGTH	LOCATION	
801	6	30'-10"	185'-0"	LONGIT. IN CAP
802	6	8'-6"	51'-0"	LONGIT. IN CAP BTW. PILES
TOTAL NO. 8 BARS = 236'-0" = 630 LBS.				
501	2	30'-10"	61'-8"	LONGIT. IN CAP
TOTAL NO. 5 BARS = 61'-8" = 64 LBS.				
401	31	8'-2"	253'-2"	STIRRUPS IN CAP
402	8	7'-6"	60'-0"	STIRRUPS IN WINGWALL
403	6	6'-6"	39'-0"	STIRRUPS IN CAP
404	4	2'-2"	8'-8"	LONGIT. IN WINGWALL
405	12	4'-0"	48'-0"	LONGIT. IN WINGWALL
TOTAL NO. 4 BARS = 408'-10" = 273 LBS.				
TOTAL DEFORMED REINFORCING STEEL = 967 LBS.				
TOTAL CLASS A1 CONCRETE = 5.79 CU. YDS.				
MAX. PILE LOAD: SERVICE DEAD LOAD = 19 TONS				
SERVICE LIVE LOAD = 36 TONS				
FACTORED TOTAL LOAD = 75 TONS				

16" ϕ PPC PILES USED FOR ESTIMATING PURPOSES ONLY. (ADD 0.04 CU. YDS. OF CLASS A1 CONCRETE PER BENT WHEN 14" ϕ PPC PILES ARE USED.) ADD 0.22 CU. YDS. OF CLASS A1 CONCRETE PER BENT WHEN ASPHALTIC CONCRETE ROADWAY PAVEMENT IS USED AT APPROACH SLAB.


ALTERNATE BENT NOTES:

DESIGN SPECIFICATIONS: AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, 4th EDITION, WITH 2008 & 2009 INTERIMS.
DESIGN LOAD: LIVE LOAD IS HL-93, AND LADV-11 (LOUISIANA DESIGN VEHICLE LIVE LOAD 2011).
STRUCTURAL CONCRETE: ALL CONCRETE SHALL BE CLASS A1. EXPOSED EDGES SHALL HAVE A 3/4" CHAMFER UNLESS SPECIFIED OTHERWISE. ALL EXPOSED FACES OF WINGWALLS AND ENDS OF CAPS SHALL RECEIVE A SURFACE FINISH AS PER THE SPECIFICATIONS UNLESS SPECIFIED OTHERWISE.
REINFORCING STEEL: ALL REINFORCING SHALL BE GRADE 60. DIMENSIONS RELATING TO FABRICATION ARE OUT TO OUT OF BARS, UNLESS OTHERWISE NOTED. DIMENSIONS RELATING TO SPACING ARE TO BAR CENTERS, UNLESS SPECIFIED OTHERWISE.
PRECAST CONCRETE PILES: CONFORM TO PILE STANDARD PLAN AND PROJECT PLANS FOR FABRICATION AND INSTALLATION. PILES WILL BE PAID FOR UNDER THE DESIGNATED PILE PAY ITEMS.
PAYMENT: ALL OTHER WORK WILL BE PAID FOR UNDER THE DESIGNATED BRIDGE SUPERSTRUCTURE AND SUBSTRUCTURE PAY ITEM AND IN ACCORDANCE WITH THE SPECIFICATIONS.


AS-DESIGNED RATING		
VEHICLE	RATING FACTOR	NOTES
HL-93 (INV)	1.649	---
HL-93 (OPR)	2.138	---
LADV-11 (INV)	1.268	MAGNIFICATION FACTOR = 1.3



STATE OF LOUISIANA
 DEPARTMENT OF TRANSPORTATION & DEVELOPMENT
 STANDARD PLAN
 ALTERNATE BENTS
 CAST-IN-PLACE CONCRETE BENT
 28'-0" CLEAR ROADWAY
 90° CROSSING TWO WAY TANGENT
 PSS-90-28-20SL
 DATE: 12/01/2025
 REVISION OR CHANGE ORDER DESCRIPTION
 APPROVED BY CHIEF ENGINEER: [Signature]
 DESIGN CHECK: B. DELATTE
 PARISH: []
 CONTROL SECTION: []
 STATE PROJECT: []
 REVIEW: D. HYVEL
 CHECK: J. NAKHLEH
 SERIES: 16 OF 11




BARRIER RAILING TRANSITION ELEVATION
 (SHOWING BARRIER RAILING AT END OF BRIDGE)
 SCALE: 1/2" = 1'-0"




GUARD RAIL CONNECTION DETAIL
 CONFORM TO GUARD RAIL STANDARD PLANS
 SCALE: 3/4" = 1'-0"


NOTE:
 THE NUTS & WASHERS FOR THE TIE ROD SHALL BE ZINC COATED AND THE EXPOSED ENDS TO THE TIE RODS SHALL BE PAINTED WITH AN APPROVED COATING. AS A FINAL OPERATION THE CONTRACTOR SHALL BE REQUIRED TO TORQUE THE INSTALLED TIE ROD TO 170 FT. LBS. JUST PRIOR TO PAINTING. ALL EXPOSED ENDS SHALL BE PAINTED WITH AN APPROVED COATING AFTER STRESSING. ONE (1) MECHANICAL SPLICE MAY BE USED IN SPLICING THE 7/8" ϕ TIE ROD. THE SPLICE SHALL DEVELOP AT LEAST 125% OF THE SPECIFIED YIELD STRENGTH OF THE TIE ROD IN TENSION. THE MECHANICAL SPLICE SHALL BE ZINC COATED OR PAINTED WITH AN APPROVED COLD GALVANIZING REPAIR COMPOUND FROM AML PRIOR TO PLACING THE TIE ROD IN THE STRUCTURE.




DETAILS OF TIE ROD




TYPICAL SECTION
 SCALE: 3/8" = 1'-0"




JOINT DETAIL
 N.T.S.




STANDARD BARRIER RAILING ELEVATION
 (SHOWING BARRIER RAILING ALONG BRIDGE END)
 SCALE: 3/8" = 1'-0"




BARRIER RAILING TRANSITION SECTIONS
 SCALE: 3/4" = 1'-0"





SECTION A-A
 SCALE: 3/4" = 1'-0"



DETAIL "A"
 SCALE: 1" = 1'-0"




DETAIL "B"
 SCALE: 1" = 1'-0"



BARRIER RAILING TRANSITION SCHEMATIC
 SCALE: 3/8" = 1'-0"


SHEET NUMBER		PARISH		STATE PROJECT	
DESIGN CHECK	B. DELATTE	CONTROL SECTION	J. NAKHLEH	REVIEW	J. NAKHLEH
DATE	12/10/2025	SERIES	7 OF 11	REVISION OR CHANGE ORDER DESCRIPTION	
APPROVED BY CHIEF ENGINEER:		DATE			
NO.		DATE			
		ALTERNATE SPAN (1 OF 4) 20'-0" CONCRETE SLAB SPAN 28'-0" CLEAR ROADWAY 90° CROSSING TWO WAY TANGENT			
		STANDARD PLAN PSS-90-28-20SL			




PRECAST BARRIER RAILING TRANSITION ELEVATION
 (SHOWING BARRIER RAILING AT END OF BRIDGE)
 SCALE: 3/4" = 1'-0"

FOR SECTION A-A & TRANSITION SECTIONS
 SEE ALTERNATE SPAN (3 OF 4)


* PLACE OR INJECT NON-SHRINK GROUT AS REQUIRED IN BETWEEN SLAB DEPRESSIONS TO FILL ALL VOIDS AND GAPS FOR FULL EVEN BEARING OF THE BARRIER ON THE SLAB. SEE NOTE 3, SHEET 9 OF 11.




STANDARD PRECAST BARRIER RAILING ELEVATION
 (SHOWING BARRIER RAILING ALONG BRIDGE SLAB)
 SCALE: 3/4" = 1'-0"




GUARD RAIL CONNECTION DETAIL
 CONFORM TO GUARD RAIL STANDARD PLANS
 SCALE: 3/4" = 1'-0"



ELEVATION
 SCALE: 1 1/2" = 1'-0"




PLAN-DEPRESSION
 SCALE: 1" = 1'-0"



PLAN-KEY
 SCALE: 1" = 1'-0"

BARRIER KEY AND PANEL DEPRESSION DETAILS


SHEET NUMBER		PARISH		STATE PROJECT	
DESIGN	B. DELATTE	CHECK	J. NAKHLEH	CONTROL SECTION	
DETAIL	D. HYMEL	CHECK	J. NAKHLEH	REVIEW	
APPROVED BY CHIEF ENGINEER:		DATE: 12/10/2025		BY	
REVISION OR CHANGE ORDER DESCRIPTION		NO.		DATE	
ALTERNATE SPAN (2 OF 4) 20'-0" PRECAST CONC. BARRIER 28'-0" CLEAR ROADWAY 90° CROSSING TWO WAY TANGENT		STATE OF LOUISIANA DEPARTMENT OF TRANSPORTATION & DEVELOPMENT		PSS-90-28-20SL STANDARD PLAN	



BARRIER RAILING TRANSITION SECTIONS




SCALE: 1" = 1'-0"

* 1" Ø THREADED STUD OF EQUAL STRENGTH, WITH 2 NUTS & 2 WASHERS, MAY BE USED IN LIEU OF H.S. BOLTS.




NOTES:


- 1) ALL BARRIER RAIL SURFACES ARE TO RECEIVE A CLASS 3 SPECIAL FINISH.
- 2) ALL SURFACES OF THE BLOCKOUTS EXCEPT THE BOTTOM MAY BE TAPERED AND ALL CORNERS MAY BE ROUNDED TO A RADIUS TO ALLOW FOR EASY REMOVAL OF PLUGS OR FORMS. AFTER PLACING AND TIGHTENING THE ANCHOR BOLTS, THE BLOCKOUTS SHALL BE FILLED WITH AN APPROVED NON-SHRINK GROUT FROM AML AND TROWELED TO THE REQUIRED FINISH AND TO THE SATISFACTION OF THE ENGINEER.
- 3) AFTER BARRIER IS PLACED AND ALIGNED, ALL GAPS UNDER BARRIER AND TOP OF SLAB SHALL BE FILLED WITH NON-SHRINK GROUT FROM AML AND ALLOWED TO SET PRIOR TO TIGHTENING OF BOLTS. IT IS IMPORTANT TO FILL ALL VOIDS AND GAPS UNDER THE BARRIER TO ENSURE EVEN BEARING ON DECK WHEN THE ANCHOR BOLTS ARE LOADED.
- 4) ALL 1" Ø BOLTS SHALL BE HIGH STRENGTH A325 OR APPROVED EQUAL. BOLT, NUT & WASHER TO BE GALVANIZED AS PER ASTM A-153. BOLTS SHALL BE TENSIONED TO 36 KIPS, OR APPROXIMATELY 540 FOOT-LB. OF TORQUE (LUBRICATED CONNECTION).





SHEET NUMBER		PARISH		CONTROL SECTION		STATE PROJECT	
DESIGN CHECK	B. DELATTE	J. NAKHLEH	CONTROL SECTION	STATE PROJECT			
DETAIL CHECK	D. HYMEL	J. NAKHLEH	REVIEW	SERIES #	9 OF 11		
APPROVED BY CHIEF ENGINEER:				DATE:	12/10/2025		
REVISION OR CHANGE ORDER DESCRIPTION							
BY							
DATE							
NO.							
ALTERNATE SPAN (3 OF 4) 20'-0" PRECAST CONC. BARRIER 28'-0" CLEAR ROADWAY 90° CROSSING TWO WAY TANGENT							
STANDARD PLAN PSS-90-28-20SL							




EXTERIOR UNIT
SCALE : 1/2" = 1'-0"



INTERIOR UNIT
SCALE : 1/2" = 1'-0"



NOTE: FOR EACH SPAN, ONE EXTERIOR UNIT WILL HAVE A TONGUE AND ONE WILL HAVE A GROOVE.



THREE (3) LAYERS OF ASPHALT SATURATED FELT SHALL BE PLACED ON TOP OF BENT CAP. CUT TAR PAPER TO EXPOSE ALL OBLONG HOLES ON TOP OF CAP PRIOR TO ERECTING THE SLAB.

2 1/2" X 5" OBLONG HOLES. HOLES SHALL BE FILLED WITH GROUT AFTER DOWEL BARS ARE IN PLACE.

NOTES:
FOR ADDITIONAL JOINT DETAILS SEE SHEET 2 OF 11.
FOR 1/2" CHAMFER DETAIL, SEE DETAIL "B", ALTERNATE SPAN 1 OF 4.

ALTERNATE SPAN NOTES:

DESIGN SPECIFICATIONS : AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, 4th EDITION, WITH 2008 & 2009 INTERIMS.

DESIGN LOAD : THE BRIDGE DECK IS DESIGNED FOR A FUTURE WEARING COURSE OF 19 PSF. THE LIVE LOAD IS HL-93, AND LADV-11 (LOUISIANA DESIGN VEHICLE LIVE LOAD 2011).

STRUCTURAL CONCRETE : ALL CONCRETE SHALL BE CLASS P1. THE BRIDGE RAIL CONCRETE SHALL BE CLASS A1 IF RAIL IS CAST IN PLACE. STEEL SIDE FORMS AND STEEL OR CONCRETE BOTTOM FORMS SHALL BE USED FOR PRECAST COMPONENTS. EXPOSED EDGES SHALL HAVE A 3/4" CHAMFER, UNLESS SPECIFIED OTHERWISE. ALL SURFACES SHALL RECEIVE A CLASS 1 ORDINARY SURFACE FINISH UPON REMOVAL OF THE FORMS. THE FINAL FINISH SHALL BE A TINE FINISH IN ACCORDANCE WITH THE SPECIFICATIONS.

REINFORCING STEEL: ALL REINFORCING STEEL SHALL BE GRADE 60. DIMENSIONS RELATING TO FABRICATION ARE OUT TO OUT OF BARS, UNLESS SPECIFIED OTHERWISE. DIMENSIONS RELATING TO SPACING ARE TO BAR CENTERS, UNLESS SPECIFIED OTHERWISE. ALL REINFORCING BARS SHALL BE PLACED TO PROVIDE A MINIMUM COVER OF 1" FROM THE DRAIN HOLES. REINFORCING STEEL MAY BE TACK WELDED FOR A DISTANCE OF NOT MORE THAN 4'-0" FROM EACH END OF UNIT. NO OTHER WELDING SHALL BE PERMITTED.

MISCELLANEOUS STEEL: HIGH STRENGTH BOLTS SHALL CONFORM TO ASTM DESIGNATION A-325. PRESTRESSING STRANDS SHALL CONFORM TO ASTM DESIGNATION A-416, GRADE 270. PLATES, TIE RODS, AND DRIFT BOLTS SHALL CONFORM TO ASTM DESIGNATION A709, GRADE 36. STEEL SPECIFIED TO BE ZINC COATED SHALL BE IN CONFORMANCE WITH ASTM DESIGNATION A-123.

GROUT: THE GROUT SHALL BE AN APPROVED FLOWABLE NON-SHRINK GROUT LISTED ON AML. THE GROUT SHALL BE TESTED FOR ACCEPTANCE PRIOR TO USAGE. THE GROUT SHALL ATTAIN A MINIMUM COMPRESSIVE STRENGTH OF 3500 PSI PRIOR TO LOADING SLABS. SURFACES SHALL BE THOROUGHLY SATURATED WITH WATER BY FLOODING THE HOLES FOR APPROXIMATELY FIVE (5) MINUTES IMMEDIATELY BEFORE THE GROUT IS PLACED. ONLY POTABLE WATER SHALL BE USED FOR SATURATION AND MIXING PURPOSES.

PATCHING MATERIAL: THE PATCHING MATERIAL SHALL BE AN APPROVED PATCHING MATERIAL FOR PRECAST OR PRESTRESSED CONCRETE PRODUCTS LISTED ON AML. SURFACE PREPARATION, MIXING AND PLACEMENT SHALL BE IN ACCORDANCE WITH THE MANUFACTURERS' RECOMMENDATIONS. ONLY POTABLE WATER SHALL BE USED FOR SATURATION AND MIXING PURPOSES.

PRECAST UNITS: THE PLANS FOR AN ONGOING OPERATION OF FABRICATION FACILITIES SHALL BE APPROVED BY THE DEPARTMENT. EACH UNIT SHALL HAVE "LIVE LOAD HL-93 & LADV-11", THE FABRICATOR'S MARK, AND UNIQUE NUMBER, MEETING THE APPROVAL OF THE ENGINEER STAMPED OR INSCRIBED IN THE PLASTIC CONCRETE. PRECAST UNITS MAY BE CAST WITH OR WITHOUT CAMBER. IF CAMBER IS PROVIDED IT SHALL NOT EXCEED 1/4" AT THE CENTERLINE OF SPAN. ALL UNITS SHALL BE HELD AT THE PLANT FOR A MINIMUM OF TEN(10) DAYS AFTER CASTING. THE CONCRETE SHALL REACH A MINIMUM STRENGTH OF 3,000 PSI BEFORE HANDLING IS PERMITTED. THE LIFTING INSERTS SHALL BE 1", TYPE S INSERTS AS MANUFACTURED BY DAYTON-SUPERIOR CORPORATION OR AN APPROVED EQUAL. EACH INSERT SHALL HAVE A MINIMUM LOAD CAPACITY OF 10,000 POUNDS. FOUR(4) INSERTS WITH 1" ϕ X 5" LONG COIL BOLTS SHALL BE PLACED IN THE TOP OF THE UNIT AND LOCATED 1'-3" FROM ITS ENDS AND 1'-0" FROM ITS EDGES. INSERT HOLES SHALL BE GROUT FILLED AFTER PLACEMENT OF UNIT. AT THE CONTRACTOR'S OPTION A SLING OF SUFFICIENT CAPACITY MAY BE USED FOR LIFTING, PROVIDED THE SAME PICKUP LOCATION FROM THE ENDS ARE USED. FABRICATION TOLERANCES SHALL BE AS FOLLOWS:

- UNIT DEPTH $\pm 3/16"$
- UNIT LENGTH $+ 1/8"$ AND $-1/2"$
- OVERALL SPAN WIDTH $\pm 2"$

ALL PRECAST UNITS IN EACH BRIDGE SPAN SHALL BE MATCH CAST IN THE SAME CASTING BED TO ENSURE A PROPER FIT DURING INSTALLATION.

GUARDRAIL: CONFORM TO PROJECT PLANS AND GUARD RAIL STANDARD PLANS.

PAYMENT: ALL WORK WILL BE PAID FOR UNDER THE DESIGNATED BRIDGE SUPERSTRUCTURE AND SUBSTRUCTURE PAY ITEM AND IN ACCORDANCE WITH THE SPECIFICATIONS.


ESTIMATED QUANTITIES (ONE EXTERIOR UNIT)

BAR NO.	UNIT LENGTH	TOTAL LENGTH	LOCATION
901	8	19'-9"	LONGIT. BOT. OF SLAB
902	1	19'-1"	LONGIT. BOT. OF SLAB
TOTAL NO. 9 BARS = 177'-1" = 602 LBS.			
801	1	1'-0"	DOWELS
TOTAL NO. 8 BARS = 1'-0" = 3 LBS.			
501	90	3'-0"	TRANS. TOP & BOT. OF SLAB
502	6	4'-6"	BOT. END OF SLAB
503	2	4'-8"	TOP END OF SLAB
TOTAL NO. 5 BARS = 306'-4" = 320 LBS.			
401	4	19'-9"	LONGIT. TOP OF SLAB
TOTAL NO. 4 BARS = 79'-0" = 53 LBS.			
DEFORMED REINFORCING STEEL = 977 LBS.			
CLASS P1 CONCRETE = 2.05 CU. YDS.			
CONCRETE RAILING (PER SPAN) = 40.00 LIN. FT.			

ESTIMATED QUANTITIES (ONE INTERIOR UNIT)

BAR NO.	UNIT LENGTH	TOTAL LENGTH	LOCATION
901	8	19'-9"	LONGIT. BOT. OF SLAB
902	1	19'-1"	LONGIT. BOT. OF SLAB
TOTAL NO. 9 BARS = 177'-1" = 602 LBS.			
801	1	1'-0"	DOWELS
TOTAL NO. 8 BARS = 1'-0" = 3 LBS.			
503	2	4'-8"	TOP END OF SLAB
504	44	3'-8"	TRANS. BOT. OF SLAB
505	6	4'-6"	BOT. END OF SLAB
TOTAL NO. 5 BARS = 197'-8" = 206 LBS.			
401	4	19'-9"	LONGIT. TOP OF SLAB
402	17	3'-8"	TRANS. TOP OF SLAB
TOTAL NO. 4 BARS = 141'-4" = 94 LBS.			
DEFORMED REINFORCING STEEL = 905 LBS.			
CLASS P1 CONCRETE = 2.46 CU. YDS.			

BASED ON A 10" SLAB THICKNESS



AS-DESIGNED RATING

VEHICLE	RATING FACTOR	NOTES
HL-93 (INV)	1.335	---
HL-93 (OPR)	1.731	---
LADV-11 (INV)	1.027	MAGNIFICATION FACTOR = 1.3

STATE OF LOUISIANA
DEPARTMENT OF TRANSPORTATION & DEVELOPMENT

ALTERNATE SPAN (4 OF 4)
20'-0" PRECAST CONC. SLAB UNIT

28'-0" CLEAR ROADWAY
90° CROSSING TWO WAY TANGENT

STANDARD PLAN

DESIGN: B. DELATTE
CHECK: J. NAKHLEH
DETAIL: D. HYMEL
CHECK: J. NAKHLEH
REVIEW: [Signature]
SERIES # 10 OF 11


APPROVED BY CHIEF ENGINEER: [Signature]
DATE: 12/10/2025

REVISION OR CHANGE ORDER DESCRIPTION


NO. DATE

BY


PSS-90-28-20SL




SECTION A-A
SCALE $\frac{3}{8}'' = 1'-0''$





PLAN
SCALE $\frac{3}{8}'' = 1'-0''$




DETAIL A
SCALE: 1" = 1'-0"
(ASPHALT CONCRETE PAVEMENT OPTION)




JOINT DETAIL
N.T.S.
403
2" Ø PIN



SECTION ALONG C ROADWAY
SCALE: $\frac{1}{4}'' = 1'-0''$



SAWING & SEALING JOINT DETAIL
N.T.S.



TYPICAL JOINT DETAIL
SCALE: 1" = 1'-0"

NOTE: FOR ADDITIONAL JOINT DETAILS SEE SHEET 2 OF 11

ESTIMATED QUANTITIES (ONE SLAB)				
BAR NO.	UNIT LENGTH	TOTAL LENGTH	LOCATION	
801	8	1'-0"	8'-0"	DOWELS
TOTAL NO. 8 BARS = 8'-0" = 21 LBS.				
601	58	9'-7"	555'-10"	LONGIT. BOT. OF SLAB
602	20	28'-8"	573'-4"	TRANSV. BOT. OF SLAB
TOTAL NO. 6 BARS = 1,129'-2" = 1,696 LBS.				
401	32	9'-7"	306'-8"	LONGIT. TOP OF SLAB & CURB
402	11	28'-8"	315'-4"	TRANSV. TOP OF SLAB
403	14	1'-10"	25'-8"	DOWELS IN CURB
TOTAL NO. 4 BARS = 647'-8" = 433 LBS.				
TOTAL DEFORMED REINFORCING STEEL = 2,150 LBS.				
CONCRETE APPROACH SLAB = 32.22 SQ. YDS.				
ASPHALT CONCRETE = 3.0 TONS				
SAW CUT & SEAL = 27 LIN. FT.				

APPROACH SLAB NOTES:

DESIGN SPECIFICATIONS: AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS 4th EDITION, WITH 2008 & 2009 INTERIMS.
 STRUCTURAL CONCRETE: ALL CONCRETE SHALL BE CLASS A1. EXPOSED EDGES SHALL HAVE A 3/4" CHAMFER UNLESS SPECIFIED OTHERWISE.
 ASPHALT CONCRETE: TO BE THE SAME TYPE AS THE ASPHALT CONCRETE USED FOR THE APPROACH ROADWAY PAVEMENT OR OVERLAY.
 REINFORCING STEEL: ALL REINFORCING STEEL SHALL BE GRADE 60. DIMENSIONS RELATING TO THE FABRICATION ARE OUT-TO-OUT OF BARS, UNLESS SPECIFIED OTHERWISE. DIMENSIONS RELATING TO SPACING ARE TO BAR CENTERS.
 BEDDING MATERIAL: FOR DETAILS OF BEDDING MATERIAL AND UNDERDRAINS SEE APPROACH SLAB STANDARD DETAILS.
 SAWING & SEALING: THE ASPHALT CONCRETE SHALL BE SAW CUT AT THE END OF THE CONCRETE APPROACH SLAB THE ENTIRE ROADWAY WIDTH AND SEALED WHICH WILL BE PAID FOR UNDER THE DESIGNATED ROADWAY PAY ITEM.
 PAYMENT: ALL OTHER WORK WILL BE PAID FOR UNDER THE DESIGNATED BRIDGE CONCRETE APPROACH SLAB PAY ITEM AND IN ACCORDANCE WITH THE SPECIFICATIONS.

SHEET NUMBER	PARISH	DESIGN CHECK	CONTROL SECTION	STATE PROJECT
	B. DELATTE	J. NAKHLEH	D. HYMEL	J. NAKHLEH
APPROVED BY CHIEF ENGINEER:	[Signature]		DATE:	12/10/2025
REVISION OR CHANGE ORDER DESCRIPTION	NO.	DATE	BY	
ALTERNATE APPROACH SLAB 10'-0" CAST-IN-PLACE 28'-0" CLEAR ROADWAY 90° CROSSING TWO WAY TANGENT				
STANDARD PLAN				