MATERIAL		REF. TESTED BY	PURP.	SAMPLED BY METHOD	MIN. FREQ.	MIN. QUANT. CONTAINER	CERT.	SMALL	TYPICAL HANDLING TIME	REMARKS
EMBANKMENT, CUT & FILL AREAS	Density	203.12 Contractor	Quality Control	Contractor TR 401	*					*Shall check sufficient to ensure specifications are met. DOTD TR 415 or TR 418 will be completed by the Department for each
		203.07 203.08 Proj. Engr.	Accept.	Proj. Engr. TR 401	1/1000 lin ft/ 2-lane rdwy/ lift			section/lift as optimum moi	section/lift as needed for optimum moisture content and determining %	
		Dist. Lab	IA	Dist. Lab TR 401	SEE INDEPENDENT ASSURANCE PROGRAM S 701.					
	Embankment Lift (Uncompacted Thickness) or Subgrade Preparation	203.12 Contractor	Quality Control	Contractor	*					*Shall check sufficient to ensure specifications are met.
		Subgrade Preparation	203.07 203.08 Proj. Engr.	Accept.	*	1/1000 lin ft/ 2-lane rdwy/ lift				
	Moisture Content @ time of	203.12 Contractor	Quality Control	Contractor TR 403	*					*Shall check sufficient to ensure specifications are met.
	compaction	203.07 203.08 Proj. Engr.	Accept.	Proj. Engr. TR 403	1/1000 lin ft/ 2-lane rdwy/ lift				1 hr.	Test taken during or just prior to compaction operation.
	Soil on Cut Slope (for pH & PI)	203.12 Contractor	Quality Control	Contractor S 401	*				·	*Shall check sufficient to ensure specifications are
		203.06 Dist. Lab	Accept.	Proj. Engr. S 401	1/1000 lin ft/ slope/soil type	1 full sample sack			5 days	met. To determine the need for plastic soil blanket or soil modification option.

SECTION 203 EXCAVATION & EMBANKMENT (Cont'd)

MATERIAL		REF. TESTED	PURP.	SAMPLED BY METHOD	MIN. FREQ.	MIN. QUANT. CONTAINER	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	REMARKS		
GEOTEXTILE FABRIC		1019.01 Mat. Lab	Prelim. Source Approval	Dist. Lab	1/type/lot/ source/ shipment	3 lin ft/roll width of fabric*			10 days	*Sample a minimum of 18 ft²,		
		1019.01 Mat. Lab	Accept.	Proj. Engr. S 601	1/type/ shipment/ source	3 lin ft/roll width of fabric*	CD** 1 & 7	150 yd²	10 days	(QPL 61) Visually inspect seams & UV damage. Seams other than 401 or "J" shall be approved by the Materials & Testing Section. See the QA Manual. *Sample a minimum of 18 ft². **Sample when not accompanied by a CD or questionable.		
LIME	Agricultural	1018.17 Mat. Lab	Accept.	Proj. Engr. S 102								
	Hydrated or Quick Lime	1018.03	Accept./ Verif./Prelim. Source Approval	SEE SECTION 304 OF THIS MANUAL.								
NON-PLASTIC EMBANKMENT	Density	203.12 Contractor	Quality Control	Contractor TR 401	*					*Shall check sufficient to ensure specifications are met.		
		203.07 Proj. Engr.	Accept.	Proj. Engr. TR 401	1/1000 lin ft/ 2-lane rdwy/lift				½ hr.			
		203.07 Dist. Lab	I A	Dist. Lab TR 401								

SECTION 203 EXCAVATION & EMBANKMENT (Cont'd)

MATERIAL		REF.	PURP.	SAMPLED BY METHOD	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL	TYPICAL HANDLING TIME	REMARKS	
		TESTED BY				CONTAINER					
NON-PLASTIC EMBANKMENT (Cont'd)	Embankment Lift (Uncompacted Thickness)	203.12 Contractor	Quality Control		*					*Shall check sufficient to ensure specifications are met.	
		203.07 Proj. Engr.	Accept.	Proj. Engr.*	1/1000 lin ft/ 2-lane rdwy/ lift					*Check lift thickness during placement.	
	Moisture Content @ Time of Compaction	203.12 Contractor	Quality Control	Contractor TR 403	*					*Shall check sufficient to ensure specifications are met.	
	· ·	203.07 Proj. Engr.	Accept.	Proj. Engr. TR 403	1/1000 lin ft/ 2-lane rdwy/ lift	1 gal Friction top can			1 hr.		
	Sand	203.12 Contractor	Quality Control	Contractor S 401	*					*Shall check sufficient to ensure specifications are met.	
		203.09 Dist. Lab	Accept.	Proj. Engr.* S 401	1/2000 yd³	1 full sample sack		500 yd³	4 days	*The Dist. Lab will sample if material is in borrow pit.	
		203.09 Dist. Lab	IA	Dist. Lab S 401	SEE INDEPENDENT ASSURANCE PROGRAM S 701.						
	Shell	203.12 Contractor	Quality Control	Contractor S 101	*					*Shall check sufficient to ensure specifications are met.	
		203.09 Dist. Lab	Accept.	Proj. Engr. S 101	1/2000 yd³	1 full sample sack		500 yd³	4 days		
		Dist. Lab	IA	Dist. Lab S 101	SEE INDEPENDENT ASSURANCE PROGRAM S 701.						
PLASTIC SOIL BLANKET	Thickness (Compacted)	203.10 Contractor	Quality Control	Contractor	*					*Shall check sufficient to ensure specifications are met.	
		203.10 Proj. Engr.	Accept.	Proj. Engr.	1/1000 lin ft/ slope					Proj. Engr. to check lift thickness after compaction.	

MATERIAL		REF.	PURP.	SAMPLED BY	MIN. FREQ.	MIN. QUANT. CONTAINER	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	REMARKS
		TESTED BY		METHOD						
PLASTIC SOIL BLANKET (Cont'd)	Plastic Soil	203.12 Contractor	Quality Control	Contractor S 401	*					*Shall check sufficient to ensure specifications are met.
		203.10 Dist. Lab	Accept.	Proj. Engr. S 401	1/1000 yd³*	1 full sample sack		300 yd³	5 days	*Not required if tested & approved as excavation or borrow pit material.
SELECTED SOIL	In-place on Roadway	203.12 Contractor	Quality Control	Contractor S 401	*					*Shall check sufficient to ensure specifications are met.
		203.06 Dist. Lab	Accept.	Proj. Engr. S 401	1/1000 lin ft/ 2-lane rdwy or 1/2000 lin ft/ shoulder	1 full sample sack			5 days	
	Stockpile	203.12 Contractor	Quality Control	Contractor S 401	*					*Shall check sufficient to ensure specifications are met.
		203.06 Dist. Lab	Accept.	Proj. Engr. S 401	1/1000 yd³				5 days	
USABLE SOIL	Borrow Pits	203.12 Contractor	Quality Control	Contractor S 401	1 boring/ acre*					*Results shall be submitted to Dist. Lab with boring request.
		203.06 Dist. Lab	Accept.	Dist. Lab S 401	1 boring/ acre for first 5 acres 1 boring/ 2 acres there after.	½ sample sack*		100 yd³	6 days	*Min. 10 lb required for test.
	Excavation	203.12 Contractor	Quality Control	Contractor S 401	As required*	1 full sample sack				May be accepted by subgrade soil survey upon approval
		203.06 Dist. Lab	Accept.	Dist. Lab S 401	As required*	1 full sample sack		100 yd³	5 days	of the District Lab. *Sample full depth of excavation.
	Stockpile	203.12 Contractor	Quality Control	Contractor S 401	*					*Shall check sufficient to ensure specifications are met.
		203.06 Dist. Lab	Accept.	Proj. Engr. S 401	1/1000 yd³	1 full sample sack		100 yd³	5 days	Will be approved in stockpile before placing on project.
WATER		1018.01 Mat. Lab	Accept.	Proj. Engr. S 303	1/source*	1 qt Plastic bottle			21 days	*Drinkable water need not be sampled.