

- A) ALL CONDUCTORS AND CABLES FROM SIGNAL HEADS AND DETECTORS SHALL BE RUN IN UNDERGROUND CONDUIT, RISERS, ON POLES, OR ON MESSENGER CABLE AND SHALL BE RUN IN THE MOST DIRECT ROUTE TO THE CONTROLLER CABINET IN ACCORDANCE WITH THE PLANS.
- B) A SPARE LENGTH OF CABLE SHALL BE INSTALLED AS SHOWN ON LADOTD STANDARD DETAIL SHEETS LABELED "SPAN WIRE INSTALLATION DETAILS" AND "JUNCTION BOX AND PULL BOX". SIX FEET OF SPARE SIGNAL CABLE, LOOP LEAD-IN, COMMUNICATION, AND SERVICE CABLE, SHALL BE INSTALLED IN EACH BASE MOUNTED CABINET IN ACCORDANCE WITH LADOTD STANDARD SPECIFICATIONS FOR ROADS AND BRIDGES.