

SECTION 814 DRILLED SHAFT FOUNDATIONS

MATERIAL		REFERENCE	PURP.	SAMPLED BY	MIN. FREQ.	MIN. QUANTITY	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	REMARKS
		TESTED BY		METHOD		CONTAINER	DISTR.			
CONCRETE (Structural)	Mix Designs, Materials & Tests	814.02	See Section 901 of this manual.							
GRANULAR MATERIAL	Pea Gravel or Granular Material	814.02 1003.07	Accept.	----	----	----	----	----	----	Visual inspection by Proj. Engr.
REINFORCEMENT		814.02 1009 Mat. Lab*	Accept.	Proj. Engr. S 501	1/size/ source**	48 in. length	CA 1	----	10 days	*Dist. Lab in Dist. 02. **If listed on QPL 71, material with a CA (Dist. 1) need not be sampled. Sample for verification if questionable.
SLURRY		814.03(c) Contractor	Quality Control	Contractor API 13B	As needed	----	----	----	----	----
		814.03(c) Proj. Engr.	Accept.	Proj. Engr.*	----	----	----	----	----	*Contractor tests to be observed by the Proj. Engr. & documented in field book.